

# **INSTALLATION MANUAL**

INMARSAT FLEET F33
SHIP EARTH STATION

MODEL FELCOM 30





#### © FURUNO ELECTRIC CO., LTD.

9-52 Ashihara-cho, Nishinomiya 662-8580, JAPAN

Telephone: 0798-65-2111 Fax : 0798-65-4200

All rights reserved. Printed in Japan

Pub. No. IME-56470-B

(DAMI) FELCOM30

Your Local Agent/Dealer

FIRST EDITION: DEC. 2004

B :MAR. 04, 2005

\*00015048001\*



\*IME56470B00\*

# **A SAFETY INSTRUCTIONS**

### **MARNING**



Do not open the equipment unless totally familiar with electrical circuits and service manual.

ELECTRICAL SHOCK HAZARD Only qualified personnel should work inside the equipment.



Do not approach the radome closer than 1 m when it is transmitting.

The radome emits radio waves which can be harmful to the human body, particularly the eyes.

RF power density on antenna aperture	distance
100W/m <sup>2</sup>	0.35 m
25W/m <sup>2</sup>	0.65 m
10W/m²	1.00 m



Turn off the power at the mains switchboard before beginning the installation. Post a sign near the switch to indicate it should not be turned on while the equipment is being installed.

Fire, electrical shock or serious injury can result if the power is left on or is applied while the equipment is being installed.

### **MARNING**



Ground the equipment to prevent electrical shock and mutual interference.

Confirm that the power supply voltage is compatible with the voltage rating of the equipment.

Connection to the wrong power supply can cause fire or damage the equipment.

# Keep the following compass safe distances.


	Standard	Steering
Antenna Unit	0.75 m	0.45 m
Communication Unit	0.30 m	0.30 m
ISDN Handset	0.30 m	0.30 m
Facsimile	1.00 m	0.65 m
Telephone	1.30 m	0.80 m



# **TABLE OF CONTENTS**

SYS	TEI	MI CONFIGURATION	iii
EQI	JIPN	MENT LISTS	iv
1.	PL/	ANNING	1
		Placing the Antenna Unit	
		Designing the Antenna Mast	
		Mounting Dimensions of Units	
	1.4	Communication Unit Connectors	8
	1.5	Examples of Installation	g
		Placing Units	
		Grounding Considerations	
	1.8	Laying Cables	14
	1.9	Telephone Wiring	15
2.	INS	TALLATION	16
	2.1		
	2.2	Installing the Above Deck Equipment (ADE)	17
	2.3	Installing the Below Deck Equipment (BDE)	18
	2.4	Installing Optional Units	27
PAC	KIN	IG LISTS	A-1
		IE DRAWING	
UU	ILIN	IE DKAVVING	D-1
INT	ERC	CONNECTION DIAGRAM	S-1

# SYSTEM CONFIGURATION



# **EQUIPMENT LISTS**

### **Standard Supply**

Name	Туре	Code No.	Qty	Remarks
Antenna Unit	SF-130	_	1	w/cable 103154 (25 m)
Communication Unit	SF-230	_	1	
ISDN Handset	SF-870	_	1	
Terminal Adapter	QDGY911912	000-147-698	1	
Installation	CP16-03200	000-150-697	1	
Materials*	CP16-03210	000-043-445	1	
Accessories	FP16-03000	000-043-466	1	CD-ROM for communication unit

<sup>\*:</sup> See lists at the back of this manual.

### **Optional Supply**

Name	Туре	Code No.	Qty	Remarks
Facsimile	FAX-8 <mark>070</mark> P	000-043-443	1 set	For CE type, w/CP16-02601
	FAX-2850	000-043-438		w/CP16-02601
	MFC-4800J	000-043-439		Japanese version
Drum Unit	DR-10J	000-146-598	1	For above facsimile
Toner Cartridge	TN-10J	000-146-599	1	For above facsimile
Telephone	FC755D1	000-433-690	1 set	w/CP16-00511, 00512
Antenna Cover	QB05-1801	100-079-480	1	
Modular Jack Box	OP16-10	000-043-278	1	Box type
	OP16-11	000-043-279	1	Flush mount type
Modular Jack Set	OP16-13	000-043-228	1	
2-pair cable	CO-SPEVV-SB-C	000-120-792	1	For ISDN connection, 10 m
	0.2x2P	000-120-794		For ISDN connection, 20 m
		000-120-214		For ISDN connection, 30 m
		000-132-827		For ISDN connection, 40 m
		000-132-826		For ISDN connection, 50 m
1-pair cable	CO-SPEVV-SB-C	000-110-681	1	For analog telephone, 10 m
	0.2x1P	000-138-789		For analog telephone, 20 m
		000-138-790		For analog telephone, 30 m
		000-138-791		For analog telephone, 40 m
		000-138-792		For analog telephone, 50 m
Serial Printer	ML280S	000-150-443	1	

### Optional supply (con't)

Name	Туре	Code No.	Qty	Remarks
Transformer	0P16-25	004-446-850	1	Transformer E-300+cable
				100VAC→220VAC (300VA)
				For FAX-2850 or FAX-8070P
Analog Telephone	DBR104001/888	000-147-693	1	
Terminal Adapter	QDGY911912	000-147-698	1	
ISDN Wall Socket	102176	000-147-699	1	
ISDN Handset	SF-870	000-043-252	1	
Incoming Indicator	KK-893-3977	000-148-478	1	For analog telephone line
Transformer	SD-221	000-139-903	1	For Facsimile MFC-4800J
Signal Cable	S16-4-15	004-446-970	1	Cable 103776
Antenna Cable	105052	000-150-706	1	50 m
Antenna Cable	QTZC502012	000-150-708	1	140 m
AC/DC Power	PR-240-CE	000-053-373	1	
Cable (LAN)	FR-FTPC-CY *10m*	000-147-472	1	10 m
Cable (LAN)	FR-FTPC-CY *20m*	000-147-473	1	20 m
Cable (LAN)	FR-FTPC-CY *30m*	000-147-474	1	30 m
ISDN Cable (3m)	QRRM911111-3000	000-150-709	1	
ISDN Cable (10m)	QRRM911111-10000	000-015-711	1	



### 1. PLANNING

### 1.1 Placing the Antenna Unit

#### **General**

Interfering objects (especially metallic objects such as masts) near the antenna can, in the worst case, prevent reception or transmission. Further, RF radiation from the antenna will affect the human body. Keep these and the following guidelines in mind when selecting a mounting location for the antenna unit.


#### Secure unobstructed path in all directions

The ideal mounting location secures an unobstructed path between the antenna unit and the satellites, from horizontal to zenith. In order words, whatever the direction the antenna unit is pointing there are no interfering objects within the main beam (16°). While this might be feasible on some vessels, on others it is impossible due to space considerations. The antenna unit should be located at least 3 meters away from masts having a diameter less than 15 centimeters.

#### Select a location low in vibration

The maximum permissible vibration amplitude in three axis direction should be as shown in the table below. Consult with the shipyard to determine the mounting location which meets the requirements shown in the table.

Freq. Range	Max. Amplitude
4 to 1 <mark>0 Hz</mark>	2.54 mm (max. 9.8 m/s <sup>2</sup> )
10 to 15 Hz 15 to 25 Hz 25 to 33 Hz	0.76 mm (max. 6.86 m/s <sup>2</sup> ) 0.40 mm (max. 9.8 m/s <sup>2</sup> ) 0.23 mm (max. 9.8 m/s <sup>2</sup> )




Maximum amplitudes


#### Locate away from passengers and crew

Radio waves can be harmful to the human body. Since safe distances vary by country and ship construction there is no uniform formula for calculating safe distance. However, below are general guidelines.

• Personnel should not approach an area in which the radiation level is higher than 10 W/m², i.e., within 1.00 m from the radome surface.



Construct a protection fence around the antenna unit so that personnel can not approach
the antenna unit within 1.00 m. Also, to alert personnel not to approach the antenna unit,
attach the caution labels (supplied as installation materials) to any bulkhead which is at
the position of 1.00 m from the antenna unit.






#### Minimum distance from other antennas

#### HF antennas, communication/navigation antennas:

The antenna should be at least 5 meters from a HF antenna. VHF, satellite navigation antenna and other communication antennas should be at least 4 meters away.

#### Radar:

The antenna should be at least 5 meters away to protect the low noise amplifier in the radar antenna. However, if this distance cannot be secured be sure the antenna is not within the radar beam.



#### Compass safe distance

Locating the antenna unit too close to a compass can affect compass performance. The compass safe distance is 0.75 meters, steering compass, 0.45 meters, standard compass.

#### Other mounting guidelines

Other important mounting guidelines are

- Locate the antenna unit away from exhaust stacks (foreign material on the radome can interfere with reception and transmission).
- Keep the unit away from heat sources.
- Locate the unit away from places where fuels and chemical solvents are stored.
- Keep in mind the length of the cable from the communication unit is maximum 100 meters.



### 1.2 Designing the Antenna Mast

#### **General**

To facilitate servicing, construct a mast of 1500 mm in height and 60 mm in diameter. (See page 5.) The paragraphs which follow provide guidelines for selection and construction of the mast. Refer to the drawing at back of this manual.


#### **Guardrail**, platform

Fit the mast with a guardrail and platform (or steps), for serviceman's safety. (In most installations the serviceman stands on the platform while checking the radome. Thus this distance should be secured for ease of servicing.) The guardrail should be as high as possible for sufficient safety.

#### Mast strength

The mast material must be sufficiently strong to meet the demands of the marine environment. It should satisfy the following requirements.

- It must be able to support radome mass plus at least 2.5 cm of ice and snow. Special consideration should be given if the unit is operated in areas of heavy snow or freezing temperature.
- Mast bending moment must be able to withstand expected maximum pitching, rolling and wind pressure.
- To prevent resonance at low frequencies (about 5 Hz), four stays can be fixed between the mast and the mounting base.




Item	Mass
Antenna unit mass	8 kg ± 10%
Platform, guardrail mass	
Expected ice and snow	
Maximum wind pressure (at wind speed 75 m/s)	1654.9 N


#### Mounting pole and mounting base


In order to ensure long life for the antenna electronics and mechanics, the antenna must be installed properly on a specially designed pole with suitable flange and rubber gasket. Below are guidelines for installation of the mounting pole and mounting base.

- The pole serves the purpose of protecting the coax cable and its N-type male connector where it joins the N-type female connector at the bottom of the dome. Further, it is a very important part of the ventilation system of the dome; the hole in the pipe allows trapped moisture to escape from the dome.
- The face of the mounting base should be flat as possible (tolerance: within 2 millimeters of the horizontal plane).
- The mounting base should be parallel with ship's horizontal plane (tolerance: ±1°).
- The fixing bolts of the mounting base should be parallel with the ship's keel line (tolerance: ±2°).
- Weld a ground bolt (stainless steel, M10x40, local supply) to the mast within 50 cm of a fixing bolt on the antenna unit. The length of the ground wire (local supply) is 50 cm.




### 1.3 Mounting Dimensions of Units






### 1.4 Communication Unit Connectors


#### Rear connector panel



### 1.5 Examples of Installation



### **Connection examples**



### 1.6 Placing Units


#### Placing the communication unit

The communication unit should be placed in a ventilated area. To ensure adequate cooling for the unit, a 10 cm unobstructed space must be maintained above and below the unit. A space of 10 cm above the unit is also required to allow removal of units.

Locating the communication unit too close to a compass can affect compass performance. The compass safe distance is 0.30 meters for both steering and standard compasses.

For grounding, see pages 13 and 18.

Six holes through the unit's mounting plate allow the unit to be fixed to a bulkhead or a desktop.



### Placing the ISDN handset

The ISDN handset functions as a display and communication unit for alert transmission. It may also be used for normal voice communication. Up to two (2) ISDN handsets may be connected in series. The units may be installed anywhere onboard the vessel.

Four separate ISDN ports are available on the communication unit as RJ45 jacks or screw terminal blocks.

Max cable length: 100 m, 4x0.22 mm<sup>2</sup>.



#### Placing the terminal adapter

The terminal adapter may be installed almost anywhere. However, install it where vibration is minimal and locate it away from heat sources.

#### Placing the ISDN handset as a standard telephone

The ISDN handsets may be installed as standard telephones. The units may be installed anywhere onboard the vessel.

Four separate ISDN ports are available on the communication unit as RJ45 jacks or screw terminal blocks.

#### Placing the telefax (option)

A digital telefax (Group 4) can be connected to one of the ISDN outlets, or to an ISDN bus for transfer at 64 kbps rate.

An analog telefax (Group 3) should be connected to the Terminal Adapter

#### Placing the PC (user supply)

A PC w/ISDN card can be connected to one of the ISDN outlets, or to an ISDN bus for 64 kbps rate data communication for installation up to 100 m away from the communication unit.

With the PC connected to the USB/RS-232/RS-422 port it can also be used for control and configuration of the Communication Unit.

This requires that the vtLite Marine program accessible on the FELCOM CD is installed. Connection to the USB/RS-232/RS-422 port also allows 64 kbps data transmission. See the PC's user's manual.



#### Cable lengths:


• ISDN port: See "ISDN telephones/equipment" on page 27.


USB port: 3 mRS-232 ports: 3 mRS-422 port: 100 m



#### Placing analog telephones (option)

Analog 2-wire telephones can be installed anywhere onboard the vessel.





### 1.7 Grounding Considerations

A successful installation of a maritime satellite terminal must take into account the noisy environment in which the equipment shall operate.

#### **Electrical noise**

The electrical environment on board a ship is usually quite noisy. Powerful electrical installations cause voltage variations and transients, as well as low and high frequency noise. Radio and radar equipment radiate radio frequency signals which frequently impregnate cables on board with unwanted interference.

#### **Ground plane**

Most ships have a steel hull. One should think that the steel construction of the ship would constitute a good ground plane. This is often not quite true. Rust, other forms of corrosion, paint and grease, often prevent a good ground connection. A consequence of this is that high energy power distribution on board a ship can cause significant ground potential differences.

#### Antenna unit

Adequate grounding of the antenna unit depends on the fastening bolts making good contact with the top flange of the mast. This is obtained by removing paint and using supplied washers and nuts and running a ground wire (local supply) between an antenna fixing stud on the antenna unit and a ground stud (local supply) bolted to the mast. Coat the antenna fixing stud and ground stud with silicon sealant. For details, see page 17.

#### Antenna cable

The antenna coaxial cable normally has a solid or meshed metal screen which must be terminated to ground both at the antenna pedestal and at the communication unit. The supplied cable is 25 meters; lengths of 50 m and 140 m are optionally available. If the ground potential level at the two points differ, the communication unit passing through the screen of the coaxial cable can be quite strong. The antenna cable screen constitutes a heavy gauge wire, which is capable of conducting large amounts of current.


#### **Below deck equipment**

The communication unit must be provided with a good electrical connection to the ship's hull for grounding. This is obtained with the supplied ground wire. "Location and grounding of units" on page 18.

#### **Mains ground**

Mains ground is secured to the common grounding point through the external supply. It is therefore important to use the same mains branch for additional equipment connected to the communication unit (Fax, PC w/printer, etc.).

See also "Location and grounding of units" on page 18.



### 1.8 Laying Cables

#### **General**

The coaxial cable for connection between the communication unit and the antenna unit should, if possible, be laid before the equipment arrives. Make sure sufficient length of cable is ordered.

Where exposed to mechanical wear (on deck, through bulkheads, etc.), the cable should be protected by steel pipes.

Standard procedures should otherwise be followed for cabling in ship installations. Special attention to existing safety regulations is required if the cable passes through zones where there may be flammable or explosive gases. Use suitable gasproof cable glands or bushings.


#### At the communication unit

The coaxial cable from the antenna unit should be given a free end of approximately 0.5 m at the communication unit location.

#### ISDN telephone, telefax or analog telephone

Choose the position for the required wall sockets and lay the cables leaving a free end of 0.5 m. Also allow a free end of 0.5 m at the connection box.


### 1.9 Telephone Wiring



# 2. INSTALLATION

Open all boxes supplied and check the contents with the enclosed packing list. Inspect units and parts for possible transport damage.

### 2.1 Basic Installation




### 2.2 Installing the Above Deck Equipment (ADE)

#### **Unpacking**

Unpack the antenna unit carefully so as not to damage it. Check it for damage.

#### **Mounting procedure**

- 1. Place the antenna unit on the mounting base.
- 2. Fix the antenna unit to the mounting base with supplied fixing studs, nuts and washers.
- 3. Coat exposed nuts, fixing studs and washers with silicon sealant, to prevent electrolytic corrosion. Also, coat all holes for radome base fixing bolts with silicon sealant.
- 4. As shown below, run a ground wire (local supply) between any one fixing stud and a ground stud (local supply) welded to the mast.



**Note:** Do not use a rubber gasket on the mounting base. The face of the mounting base should be flat as possible (tolerance: within 2 mm of the horizontal plane). If tolerance is more than 2 mm, insert a metal spacer between the antenna bottom and the mounting base.


#### **Attach electromagnetic wave caution labels**

Labels which warn of electromagnetic waves are supplied with the installation materials. Attach them to the following locations:

- Attach one to the radome mast where it can easily be seen.
- Attach other to a conspicuous location in any stairwell leading to the deck where the antenna unit is installed.


# 2.3 Installing the Below Deck Equipment (BDE)

Location and grounding of units




#### Installation of cable strain reliever

The cable strain reliever is mounted 5-6 cm below the communication unit's front panel and directly to a bulkhead. The shield of a cable is fastened to a screw on the front panel of the communication unit.




### Example of local or nearby installation

The installation includes four ISDN handsets, Group 3 and Group 4 telefaxes, and three PCs.



#### **Example of remote installation**

The installation includes two ISDN Handsets connected to the ISDN bus via wallboxes with two 8-pin RJ45 jacks and analog telephone.



#### **ISDN** handset


Plug the ISDN handset into the ISDN socket located on the connector panel of the CU.

**Note:** It is not recommended to extend the handset cable by more than 6 m.




#### Handset holder/cradle


The handset holder/cradle may be mounted on a desktop or a bulkhead.



Attach the holder to the bulkhead or desktop with four 4 mm wood screws or self-tapping screws. (Screws should be supplied locally.)




Place the handset on the holder as shown.




#### Mounting the communication unit

Fix the unit to the chosen location with six self-tapping screws.




### Connecting the antenna cable to the communication unit

- 1. Strip the antenna coaxial cable, leaving sufficient slack for connection to the CU.
- 2. Attach the N-plug to the cable in accordance with the instructions (see the next several pages).



#### **N-P-8DFB** connector

Attach the connector to the antenna cable as shown below.




How to attach the antenna cable connector N-P-8DFB

#### **N-P-12DSFA connector**


Attach the connector to the antenna cable as shown below.

(Dimensions in millimeters.)



How to attach the antenna cable connector N-P-12DSFA

### **Terminal Adapter QDGY911912**




**Note:** The AC/DC Adapter supplied with the Terminal Adapter is designed for connection to 230 VAC. If the ship's mains is 100 VAC, use a transformer.

### 2.4 Installing Optional Units

#### ISDN telephones/equipment


ISDN equipment is connected to the ISDN outlets on the CU connector panel, either to terminal blocks or RJ45 jacks.

An ISDN bus can be connected to *one* of the ISDN outlets. Max. extension length: 100 m, min. 0.22 mm<sup>2</sup>.



Up to eight ISDN devices may be operated with the FELCOM.


#### **ISDN** connectors




#### **ISDN** bus termination

When longer than 10 meters, the end of the ISDN bus must be terminated by two resistors as shown below. Only one bus/termination per CU.

Be aware that only one ISDN cable is permitted to be longer than 10 meters.



#### PC - asynchronous data communication



#### RS-232 connector pin assignments

Pin number	Mne- monic	Circuit	DIN	CCITT circuit	Signal source	Dscription
1	CD			109	DCE	Carrier detect
2	RXD	BB	D1	104	DTE	Received Data
3	TXD	BA	D2	103	DCE	Tramsmitted Data
4	DTR			108	DTE	Data terminal ready
5	GND			102		Signal ground
6	DSR			107	DCE	Data set ready
7	RTS	CA	S2	105	DTE	Request To Send
8	CTS	СВ	M2	106	DCE	Clear To Send
9	RI			125	DCE	Ring indicator



Signal source DTE means that the signal goes from the PC to FELCOM.

Signal source DCE means that the signal goes from FELCOM to the PC.

#### Signal descriptions

102 Signal Ground

Digital ground, return line.

103 Send Data

Data transmitted from DTE (PC) to DCE (FELCOM).

104 Receive data

Data Received from DCE (FELCOM) to DTE (PC).

105 Request To Send

OFF requests DCE (FELCOM) to suspend transmission to DTE (PC).

ON requests DCE (FELCOM) to resume transmission to DTE (PC).

106 Clear to send

OFF indicates that DCE (FELCOM) cannot accept data from DTE (PC).

ON indicates that DCE (FELCOM) is prepared to accept data from DTE (PC).

107 Data Set Ready

Signal from FELCOM that when ON indicates that a data call setup is in progress.

108 Data Terminal Ready

Signal from PC. This signal is used in the Hotline mode and indicate when going from OFF to ON that the PC wants to make a data call. The PC clears the call by setting the signal from ON to OFF.

109 Receive Signal Indicator

Signal from FELCOM that when ON indicates that connection is established and received data will be delivered on circuit 104, Received Data.

125 Ring Indicator


Signal from FELCOM. This signal is used in the Auto answer OFF mode and when ON indicates that an incoming call is in progress. The signal will go OFF when the call is answered by the PC by turning circuit 108 Data Terminal Ready ON.

### Facsimile FAX-8070P (for CE type) /FAX-2850


Refer to the drawing below. Use only the installation materials supplied.

Note: When ship's main is 110/115 VAC, the optional Transformer E-300 is required.

1. Attach four "rough" hook & loop fasteners (2) to the bottom of the facsimile as shown in the drawing below.




2. Attach four "smooth" hook & loop fasteners (1) to the facsimile fixing plate as shown below.




3. Attach the compass safety distance label at the right side as shown below.



4. Fasten the facsimile fixing plate to the mounting location with five self-tapping screws.



5. Set the facsimile on top of the facsimile fixing plate.



#### **Telephone FC755D1**

#### **General**

The telephone can be installed on a desktop or a bulkhead. Select a location where the telephone can easily be operated.

- For installation on a wooden table, use the mounting base and self-tapping screws (supplied).
- For installation on a steel table, fix the telephone with nuts and bolts.
- For bulkhead mounting, use the bulkhead mounting base (supplied with telephone accessories).


#### **Mounting location**


Select a location where temperature and humidity are moderate and stable. Secure sufficient space around the unit for ease of operation and maintenance.

#### **Mounting**


The mounting dimensions are given in the outline drawing at the back of this manual. Determine the mounting location, leaving sufficient space around the unit, and then fix the mounting base to the mounting location. The mounting base is different for bulkhead and desktop mounting, however the mounting procedure is the same for all.

- Fix the mounting base to the mounting location with four self-tapping screws (4x16).
- 2. On the underside of the telephone, unfasten the screw shown in the figure. (The screw may be discarded.) Attach vulcanizing tape (supplied) to the handset fixture. Fasten the handset fixture to the underside of the telephone with a screw (3x14, supplied).
- 3. The catch in the receiver cradle functions to hang up the handset completely. Set the catch in the upward position as shown in left. (To detach the handset from the hanger, slide the handset upward.)





- 4. Set the telephone to the four catches in the mounting base and then slide it toward you until you hear a click.
- 5. Attach the "SLIDE" label (supplied) to the handset.
- 6. Attach English language label (supplied) to the telephone.
- 7. Attach the label (16-007-6927-0) for compass safe distance as shown below.




Telephone, attaching the label

### Serial printer ML280S

Set the DIP switches in the ML280S as shown below. These switches are under the small cover on the top of the printer. (See the printer's manual for the location.)

#### Switch bank 1


Switch no.	OFF	ON	FUNCTION
1	Even	Odd *	Parity
2	With	No *	Parity
3	7	8 *	Databits
4	X-on/X-off	Ready/Busy *	Protocol
5	Monitor	Circuit *	Test Select
6	Test	Print	Mode Select
7		ON *	Busy line
8	Off *		RTS (-9V) pin 4



#### \* Correct setting

#### Switch bank 2

Switch no.	OFF	ON	FUNCTION				
1		ON *					
2	Off *		Baud rate 4,800				
3		ON *	] 4,000				
4	Invalid	Valid *	DSR I/P Signal				
5	512 Bytes	32 Bytes *	Bufer Threshold				
6	1 sec.	200 ms *	Min. Busy Time				
7	High when selected	High at Power on *	DTR Signal				
8	*		Not Used				



16AN-X-9851

PACKING

1/2

\T'\0		_		-		+		-	*)	CP16-03210	9		-		<b>/</b> -	
DESCRIPTION/CODE		SF-130	000-043-516	SF-230	000-043-517	SF-870	000-043-349		999-999-052		QSBF119048-0320	000-150-699	100001	000-150-698	R906686	
OUTLINE		φ 400			310	198		290	105	COMMUNICATION UNIT INSTALL	30	E) hamman 1 4 5		NE=1		
NAME	コニット リッコ	アンテナコニット	ANTENNA UNIT	通信制御ユニット	COMMUNICATION UNIT	I SDNバント <sup>*</sup> セット	ISDN HANDSET	9-ミルアダプタ(箱詰品)	TERMINAL ADAPTEER	通信制御用工材 COMM	取付衫	FIXING SCREW	USB <b>7-</b> 7	USB CABLE	ケーブ ル組品	

NAME	OUTLINE	DESCRIPTION/CODE	Q'TY
アース線		L3000	<del>       </del>
GROUNDING WIRE	3m	999-999-053	(1,1)
りシンプ。金具	164		15
CABLE STRAIN RELIEVER	International designation of the second desi	939-968-058	(£)
7-7端子衫	23		
EARTH TERMINAL SCREW		999-999-057	(*1)
ISDNIVY 164 H 付属品 ISDN	ISDN HANDSET ACCESSORIES		
ハンド セットホルダ —	001	QSXA911394	-
HAIND SEI HULDER		000-147-689	3
通信制御用付属品 COMM	COMMUNICATION UNIT ACCESSORIES	IES	
CD-ROM	142	1650178	1
CD-ROM		004-447-930	
アゲエ材 ANTEI	ANTENNA INSTALLATION MATERIALS	ST	
アンテナ固定ボルト	55	M8X55	4
FIXING STUD	(IIII)   (IIII)   (148	000-000-066	(*1)
八木座金	15	M8 SUS304	4
SPRING WASHER	9	000-864-262	
六角ナット 1種		M8 SUS304	8
HEX.NUT	13	000-863-110	

1.1-ド番号末尾の[\*\*]は、選択品の代表型式/1-ドを表します。 CODE NUMBER ENDING WITH "\*\*" INDICATES THE CODE NUMBER OF REPRESENTATIVE MATERIAL.

000-150-696

L=9.8M

POWER CABLE

電源ケ-ブル

102528

2.(\*1)は、タミーコードに付き、注文できません。 (\*1)THIS CODE CANNOT BE ORDERED. Q'TY

DESCRIPTION/CODE

OUTLINE

NAME

2/2

16AN-X-9851 -1

ш	
30-J/E	
ஜ்	
FELCO SOUTH	
2	
벋	
-	•
S	)
	-

PACKING

								<b>)</b>							
Q'TY	4		1	(*1)	1			1		1		7		1	
DESCRIPTION/CODE	M8 SUS304	000-864-130		999-999-054	103154	000-150-697		0SJ-56470-*	000-150-481 **	OMJ-56470-*	000-150-477 **	J5-95001-0*	000-807-330	IMJ-56470-*	
OUTLINE	<u>\$</u>		190			L=25M	MENT	210	297	210		210	297	210	297
NAME	ミガ キ平座金	FLAT WASHER	<i>N</i> ህ <b>ኛ</b> – <i>ウ</i> (DANGER)	LABEL(DANGER)	<i>ጉን</i> ታታታ–ን	ANTENNA CABLE	<b>図書</b> DOCUMENT	操作要領書(和)	OPERATOR'S GUIDE	取扱説明書(和)	OPERATOR'S MANUAL	<i>ጉ</i> ን° ሀ <i>ケ-</i> ションフォ-Δ	REGISTRATION FOR SERVICE ACTIVATION	装備要領書(和)	

_			-		_						1		7
	200	000-150-481 **	OMJ-56470-*	000-150-477 **	J5-95001-0*		000-807-330	IMJ-56470-*		000-150-479 **	C52-00402-*		000-150-529
	297		617		210	297		× 210	297		× 012	297	
[* F文성  (개 /	OPERATOR'S GUIDE		取扱説明書(和)	OPERATOR'S MANUAL	<i>የ</i> ን° ሀ <i>ケ</i> –୬ョンフォ-Δ		SERVICE ACTIVATION	装備要領書(和)	I VI II V V V V V V V V V V V V V V V V	INCIALLATION WANDAL	アナユン・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・・	CALITION FOR	INSTALLATION

1.1-ド番号末尾の[\*\*]は、選択品の代表型式/1-ドを表します。 CODE NUMBER ENDING WITH "\*\*" INDICATES THE CODE NUMBER OF REPRESENTATIVE MATERIAL.

2.(\*1)は、タミーコードに付き、注文できません。 (\*1)THIS CODE CANNOT BE ORDERED.

	URUN	_	CODE NO.	004-430-050	)	16AI-X-9407 -2	
			TYPE	CP16-02601		1,	/1
エ	事材料表	For FAX-8070P/28	350				
INST	ALLATION MATERIALS						
番号 NO.	名 称 NAME	略 図 OUTLINE		名/規格 RIPTIONS	数量 Q'TY	用途/備考 REMARKS	
1	ハリマーク(INMAR) LABEL (INMAR)	20 ( ( ( ) ( ) ( ) ( )	16-007-69	919-0	1		
		20 ( )	CODE NO.	100-217-010			
	ハリマーク	62	16-007-69	927-0			
2	LABEL	(1) 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	CODE NO.	100-222-480	1		
	取付板	374	16-011-31	101-1			
3	MOUNTING PLATE	274	CODE NO.	100-303-181	1		
			OODL NO.	100-303-101			
4	フック押え板	40	16-011-31	102-0	1		
	HOOK RETENTION PLATE	48	CODE NO.	10 <mark>0-3</mark> 03-190	1		
_	マシ゛ックテーフ゜(1)	165	16-011-31	103-0			
5	ROOP FASTENER(1)	25. 4	CODE NO.	100-303-200	4	7	
	マシ゛ックテーフ゜(2)	<del>&lt; 165 →</del>	16-011-31	104-0			
6	ROOP FASTENER(2)	25. 4	CODE NO.	100-303-210	4		
	+トラスタッピンネジ		5X20 SUS3	304 1ÿı			
7	+TAPPING SCREW	20	3/120 0000	707 171	5		
		( )	CODE NO.	000-802-081			
	FAX取付手順書	210	C52-00204	1-A			
8	FAX INSTALLATION PROCEDURES	731	CODE NO.	000-146-784	1		

FURUNO ELECTRIC CO .,LTD. (略図の寸法は、参考値です。 DIMENSIONS IN DRAWING FOR REFERENCE ONLY.)


	URUI		CODE NO.	004-438-410	)	16AG-X-9412 -0
			TYPE	CP16-00511		1/1
	事材料表 ALLATION MATERIALS	For Telephone F	C755D1			
番 号 NO.	名 称 NAME	略 図 OUTLINE		!名/規格 CRIPTIONS	数量 Q'TY	用途/備考 REMARKS
4	ハリマーク(SLIDE) LABEL(SLIDE)	20 25	16-007-6	405-0	1	
	LABLE (SETBE)	SLIDE	CODE NO.	100-222-470		
0	ハリマーク(INMAR)	20 0 2	16-007-6	919-0	1	
_	LABEL (INMAR)	20 (18)	CODE NO.	100-217-010		
	ハリマーク	62	16-007-6	927-0		
3	LABEL	<u> </u>	CODE NO.	100-222-480	1	
	受話器固定具	30	16-011-7	101-1		
4	HANDSET FIXTURE	50	CODE NO.	100 <mark>-27</mark> 3-831	1	
	接着テープ	30	16-011-7	103-0		
5	VULCANIZING TAPE	28	CODE NO.	100-273-940	1	7
	キーシール	25	16-011-7	111-0		
6	LABEL	30	CODE NO.	100-273-850	1	
	シート(TEL.)	86	16-011-7	112-0		
7	SHEAT(TEL.)	98			1	
	1.* Db (1.b)*		CODE NO.	100-273-860		
8	+ţ^* P91トネジ	<u> ≈ 14 →  </u>	3X14 SWC	H18A MFZN-2-C	1	
	SCREW	$0 \qquad \qquad$	CODE NO.	000-800-172	'	
	+トラスタッピ ンネジ	<u> 16</u> →	4X16 SUS	304 1>๋า		
9	+TAPPING SCREW	() pulled 1 \$\phi 4\$	CODE NO.	000-802-080	4	
	型 型 型 型 型 型 型	103	FC755WM	<u> </u>		
10	MOUNTING BASE	123	CODE NO.	000-808-704	1	


16AG-X-9412


FURUNO ELECTRIC CO ., LTD. (略図の寸法は、参考値です。 DIMENSIONS IN DRAWING FOR REFERENCE ONLY.)


		-					
	URUI		ODE NO.	004-438-420	)	16AG-X-9413 -0	
		Т	YPE	CP16-00512			1/1
I	事材料表	For Telephone FC	755D1				
INST	ALLATION MATERIALS						
番 号	名 称	略図	型:	名 / 規格	数量	用途/備考	
NO.	NAME	OUTLINE	DESC	CRIPTIONS	Q'TY	REMARKS	
1	取付板 MOUNTING BASE	103	16-011-71 CODE NO.	100-273-840	. 1		
2	+Իラスタッピンネジ +TAPPING SCREW	16 100000 1 \$\phi\$ 4	4X16 SUS3	304 1>๋า 000-802-080	4		


16AG-X-9413




















www.reelschematic.com FURU S-1 100/110 /200/220VAC SF-130 ISDN HANDSET SF-8 ISDN WALL SOCKET TERMINAL ADAPTOR HANDSET SF-8 I WALL SOCKET INAL ADAPTOR 12-24VDC 12-24VDC アンテナユニッ ANTENNA UNIT 2.72 DPYC-1.5 \*1\_\_\_\_\_12.8 ISDN H Α Ac IN I SUPPLY SUPPLY UNIT \*\*\*\* ISDN CABLE : 1 ·ット SOCKET | AC/DC電源三 | AC/DC POWER & PR-240-CE | ISDN W| | 102176 | SF-870 ISDN壁ソケッ ISDN WALL S 102176 105052,50m (0PTION) 0TZC502012,140m (0PTION) ISDN/ソドセット ISDN HANDSET SF-870 15 15 15 /CS-10, 103776, N-P-12DSFA \* \* \* \* \* 1 2 3 4 5 6 7 8 \*5 \*6 \* \* \* \* ISDN 通信制御ユニット COMMUNICATI<mark>ON</mark> UNIT SF-230 1 2 3 4 5 6 7 1 2 3 4 5 6 7 1 2 3 4 5 6 7 ± L3000, 3m TLLLLLLL, زنزنزنز USB CABLE 100001 MAX 3 m 8 MAX 3 m X F C - F STRA IGHT RS232C CABLE
MAX 3 m
Z F L - F
STRA I GHT RJ-45 <u>~</u>.... KK-893-3977 \_\_<u>~~~</u>| | パソコン \*4 | PC |シリアルプリンタ |着信指示器(ベル) |INCOMING INDICATOR ターミナルアダプタ TERMINAL ADAPTOR QDGY911912 航法装置 || NAV EQUIPMENT|| ! パソコン \*4 RS422-RS232C トランス(P) \*2 STEP-DOWN TRANS. \_\_\_\_PC\_\_\_\_\_ L\_\_\_^^ SERIAL PRINTER SERIAL PRINTER S: 接続箱 JUNCTION BOX ACT & T パソコン \*4 PC 220-230 VAC, 1 ,50-60 Hz 「」 「」 「」 「ファケシミリ \*2 「FACS I MILE 「FAX-2850 ステップ<sup>°</sup> アップ<sup>°</sup> トランス STEP-UP TRANS. RJ-11 230VAC ,50-60Hz E-300 FAX-8070P MFC-4800J 2.5m 101818, 2m 電話 TELEPHONE (FC755D1)
アナログ電話機 一く。ANALOGUE TELEPHONE DBAR104001/888 무. 100-115 VAC, D 1 ,50-60 Hz (FOR MFC-4800J) 100VAC FELCOM 30 Mar. 3 '05 D. MILLS \*5: 1つのポートの総ケーブル長は100m。 CABLE LECGTH FOR ONE PORT IS 100 m. 注 記: \*1:造船所手配 着信指示器(KK-893-3977)を挿入可能 INCOMING INDICATOR CAN BE INSERTED. 名称 CHECKED インマルサットFLEET F33 船舶地球局 TAKAHASHI.T \*6: ISDN同等機器を接続 ISDN OR EQUIVALENT CAN BE CONNECTED \*2:オプション OPTION 着信指示器は直列または並列に接続可能 APPROVED INCOMING INDICATOR CAN BE CONNECTED IN PARALLEL OR IN SERIES. 相互結線図 \*3: ブラグは工場にて取付済 \*7: 電話同等機器を接続
PLUG FITTED AT FACTORY. \*7: 電話同等機器を接続
TELEPHONE OR EQUIVALENT Y. Hatai RS-422またはRS-232Cをメニューで選択可能 TELEPHONE OR EQUIVALENT CAN BE CONNECTED. SCALE MASS NAME RS-422, RS-232C SELECTABLE FROM MEMU \*4: ユーザー手配 USER SUPPLY INMARSAT FLEET F33 MES DWG No. INTERCONNECTION DIAGRAM C5647-C01- B

FURUNO ELECTRIC CO., LTD.